

OFFICE OF STATE AID ROAD CONSTRUCTION
MISSISSIPPI DEPARTMENT OF TRANSPORTATION
AND
ITAWAMBA COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed or electronic bids will be received by the Board of Supervisors of Itawamba County, Mississippi until 10:00 AM on the 10th day of October and shortly thereafter publicly opened for the construction of 0.099 miles of PRECAST CONCRETE BRIDGE AND APPROACHES TO REPLACE BRIDGE 109 on Mount Pleasant Road being known as Project No. LSBP-29(34) in Itawamba County, Mississippi. Sealed bids will be received until the designated date and time at the Itawamba County Courthouse, 201 West Main Street, Fulton, Mississippi or electronic bids will be received until the designated date and time via electronic online bid submission through www.cceplanroom.com.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

<u>ITEM</u>	<u>QUANTITY</u>	<u>UNIT</u>
<u>ROADWAY ITEMS:</u>		
MOBILIZATION	LUMP SUM	LS
CLEARING AND GRUBBING	LUMP SUM	LS
REMOVAL OF EXISTING BRIDGE AT sta. 24+03	1.000	UN
BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9)	2,290.000	CY
GEOTEXTILE FABRIC STABILIZATION (TYPE V) (AOS <0.43)	1,298.000	SY
CRUSHED STONE (SIZE 3/4" AND DOWN)(FM)	267.000	CY
24" REINFORCED CONCRETE PIPE, CLASS III	80.000	LF
RIGHT-OF-WAY MARKERS (TYPE II)	8.000	EA
MAINTENANCE OF TRAFFIC	LUMP SUM	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS)(TYPE 3)	4.000	EA
<u>EROSION CONTROL ITEMS:</u>		
AGRICULTURAL LIMESTONE	2.000	TON
COMMERCIAL FERTILIZER (13-13-13)	1.000	TON
SEEDING	1.000	AC
SOLID SODDING	100.000	SY
EXCELSIOR BLANKET	3,852.000	SY
TEMPORARY SILT FENCE (TYPE I OR II) (AOS 0.15-0.84)	625.000	LF
WATTLES, 20"	280.000	LF
<u>BRIDGE ITEMS:</u>		
TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" PRESTRESSED CONCRETE PILING	870.000	LF
24" PRE-FORMED PILE HOLES	732.000	LF
40' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR, 30 DEG SKEW, RT FWD	24.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR, 30 DEG SKEW, RT FWD	8.000	EA

SECTION 900
PROJECT NO. LSBP-29(34)
ITAWAMBA COUNTY

PRECAST CONCRETE BARRIER RAIL	320.000	LF
36.25' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE, 30 DEG SKEW, RT FWD.	3.000	EA
36' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE, 30 DEG SKEW, RT FWD.	2.000	EA
11.0' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 200 LB.	174.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS <0.43	322.000	SY

NOTICE TO CONTRACTORS:

CONTRACT TIME: 75 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The Board of Supervisors hereby notifies all bidders that it will affirmatively ensure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Itawamba County, the LSBP Engineer's office and the Office of the State Aid Engineer, 412 E. Woodrow Wilson Avenue, Jackson, Mississippi. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Carrson Neal, LSBP Engineer for Itawamba County, Mississippi, at www.cceplanroom.com. The cost is fifty dollars (\$50.00) for plans and fifty dollars (\$50.00) for the proposal, non-refundable. PLANS AND PROPOSALS may also be downloaded electronically for an additional \$25 fee by Bidders for electronic bidding purposes only. Questions regarding electronic bidding shall be directed to Plan House Printing (662)407-0193.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Itawamba County and the State of Mississippi must accompany each proposal. For bidders submitting bids electronically, the bond submitted must be either a bond issued by the Surety in electronic format or the original hard copy of the bid bond must be submitted to the Itawamba County Board of Supervisors, 201 W. Main Street, Fulton, MS prior to the bid opening in order for the bid to be valid.

The entire PROPOSAL is required to be turned in for both paper and electronic bid submission.

Bids will be accepted only under the name of the Bidder to whom PLANS AND PROPOSALS have been issued by the County Engineer, and whose name appears on the official list of Planholders maintained by the County Engineer.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Ike Johnson, President
Itawamba County Board of Supervisors